



**CATALYST CAMPUS  
REBAR**

Item #	Scope of Work	Qty +/-	Type	LBS	Amount	Notes
1	Mobilizations	4	EA			It is anticipated that multiple mobilizations will be required due to the phasing of the work.
2	EXTERIOR					
3	Concrete Pavement - Grade 60	1,750	SF	2,625		
4	Concrete Bench (2'Wx3'H) - Grade 60	1	EA	55		
5	Concrete Bench (1'Wx3'H) - Grade 60	1	EA	55		
6	INTERIOR					
7	FC3 - 3'W x 1'H - Grade 60	40	SF	55		
8	FC4 - 4'W x 1'H - Grade 60	57	SF	82		
9	2'W x 1'H - Grade 60	15	SF	20		
10	3'W x 2'H - Grade 60	160	SF	440		
11	3'-6"W x 1' H Concrete Bench Footing - Grade 60	285	SF	400		
12	1'-4" x 2'W x 4" H Footing - Grade 60	5	SF	5		
13	F3 - 3' x 3' x 1'H - 2 EA - Grade 60	25	SF	30		
14	F5 - 5' x 5' x 1'H - 1 EA - Grade 60	30	SF	40		
15	F6 - 6' x 6' x 1'H - 2 EA - Grade 60	85	SF	115		
16	FC23 - 2'W x 3'L x 1'H - 2 EA - Grade 60	18	SF	20		
17	Helical Core Drill Footing - 1'-4" x 1'-8"H - 2 EA - Grade 60	2	EA	20		
18	SHOTCRETE WALL					
19	Epoxy Coated Rebar - Grade 60	1,066	SF	320		
20	Rebar - Grade 60	1,066	SF	1,735		
21	CONCRETE WALL - Grade 60	333	SF	820		
22	CONCRETE COLUMNS - 1'-6" Diameter - Grade 60	3	EA	615		
23	SLAB ON GRADE - Grade 60	200	SF	300		
24	CONCRETE SLAB - Grade 60	285	SF	930		
25	CONCRETE STAIRS - Grade 60	145	LF	405		
26	MASONRY - Grade 60	420	SF	445		
27	Other _____					
28	Other _____					
29	Other _____					
30	<b>TOTAL:</b>			9,532		

**Notes**

- 1 Quantities are the responsibility of the subcontractor. The above quantities are for reference only. Should any discrepancies arise, the subcontractor is to notify the General Contractor and utilize the quantities needed to provide a complete package.
- 2 The above "Other" line items are for any additional items the concrete contractor feels that need to be included to provide a complete and fully functional package.
- 3 Permits and impact fees to be paid by General Contractor (reimbursed by Owner).
- 4 Acknowledgement of Addenda: