



**CATALYST CAMPUS
STEEL**

Item #	Scope of Work	Qty +/-	Type	LBS	Amount	Notes
1	Mobilizations	1	LOT			It is assumed for this scope of work, multiple mobilizations will be required throughout the course of the project.
2	Erection/Installation	1	LOT			
3	14"x7"x1/2" Base Plates	14	EA	195		
4	HSS3x3x1/4 Galvanized Post	2	EA	229		
5	HSS4x4x1/4	7	EA	1,111		
6	HSS6x2x1/4	5	EA	793		
7	HSS6x6x1/4	2	EA	286		
8	HSS12x6x1/4	1	EA	1,350		
9	HSS14x4x1/4	1	EA	473		
10	(2" DIA) 4'L STD Pipe parapet brace	1	EA	92		
11	C6x13	1	EA	420		
12	C12x20.7	1	EA	1,485		
13	L3x3x1/4	1	EA	79		
14	L6x6x1/2 Galvanized Angle	1	EA	396		
15	Steel stair stringer	1	EA	145		
16	Steel riser w/ Clip angle	220	LF			
17	(36"Hx1-1/2" DIA) Painted Steel pipe handrail.	12	LF			
18	(44"H) Handrail.	360	LF			
19	(36"H) Wall mounted handrail.	50	LF			
20	(42"H) Guardrail.	30	LF			
21	(6'-11"H) Guardrail	16	LF			
22	(14"W) Roof access ladder.	26	LF			
23	Misc. Items	1	LS			
24	Other _____					
25	Other _____					
26	Other _____					
27	TOTAL:					

Notes

- 1 Quantities are the responsibility of the subcontractor The above quantities are for reference only Should any discrepancies arise, the subcontractor is to notify the General Contractor and utilize the quantities needed to provide a complete package
- 2 The above "Other" line items are for any additional items the concrete contractor feels that need to be included to provide a complete and fully functional package
- 3 Permits and impact fees to be paid by General Contractor (reimbursed by Owner)
- 4 Acknowledgement of Addenda: