



**CATALYST CAMPUS  
CERAMIC TILE**

Item #	Scope of Work	Qty +/-	Type	Amount	Notes
1	Mobilizations	1	LOT		It is assumed for this scope of work, multiple mobilizations will be required throughout the course of the project.
2	(8"x8") Type T1, Floor tile. (Manuf: MARAZZI TILE - D_SEGNI PARISIAN MOUL - CHALK / MIDNIGHT/SHADOW/SMOKE BLEND)	530	SF		
3	(8"x8") Type T2, Restroom Floor tile. (Manuf: MARAZZI TILE - S_SEGNI KALEIDO MOUH - CHALK / MUD/SMOKE/ MIDNIGHT BLEND)	845	SF		
4	(8"x8") Type T4, Floor tile. (Manuf: MARAZZI TILE - D_SEGNI STELLA MOUA - CHALK / MIDNIGHT/SHADOW/SMOKE BLEND)	280	SF		
5	(4"x16") Type T-3, Wall tile. (Manuf: FLORIDA TILE - STREAMLINE - ARCTIC MATTE)	2,525	SF		
6	(8"x8") Type T-5, Wall tile. (Manuf: MARAZZI TILE - D_SEGNI STELLA MOUA - CHALK / MIDNIGHT/SHADOW/SMOKE/DENIM)	215	SF		
7	(8.5"x10") Type T-6, Wall tile. (Manuf: CONTEMPO - WOW COLLECTION (3D) - GRAPHIC MATTE)	25	SF		
8	Wood floor to Tile floor Transition(Schluter schiene satin anodized aluminum)	77	LF		
9	Wood floor to carpet Tile floor Transition(Schluter schiene satin anodized aluminum)	65	LF		
10	Misc	1	LOT		
11	Other _____				
12	Other _____				
13	Other _____				
14	<b>TOTAL:</b>				

**Notes**

- Quantities are the responsibility of the subcontractor The above quantities are for reference only Should any discrepancies arise, the subcontractor is to notify the General Contractor and utilize the quantities needed to provide a complete package
- The above "Other" line items are for any additional items the concrete contractor feels that need to be included to provide a complete and fully functional package
- Permits and impact fees to be paid by General Contractor (reimbursed by Owner)
- Acknowledgement of Addenda: